

Identification Phase

Assessment Phase

Control Phase

Completion Phase

Is it likely that Asbestos is present in linings to be disturbed during the required works



Identify linings to be disturbed
Review ACM register

Possible ACM

Install Strip Out Controls

Linings Removal

Lining Disposal

Update Risk Assessment & Customer Notification

NO

Provide Documentation & Update ACM Register

Reviewed by: Brendan Riordan


As at 19 November 2020

Approved by: Ray Formosa



YES

Sample Test to Confirm



Negative

Update Risk Assessment & Customer Notification

Set Up Air Monitoring & Removal Process

ACM Removal Clearance Certificate

Positive

Follow Asbestos Removal Process

Work Cover Notification

ACM Removal

ACM Disposal